

Glenn Research Center Centralized Office Building

Preliminary Design Review (PDR)


May 14, 2009

***NASA Facilities Engineering & Real Property Symposium
Langley Research Center***

Glenn Research Center

Facilities Division

Lewis Field & Plum Brook Station



Why Is Glenn Doing a PDR?


- **Introduction by Mark Woodling**
- **GRC Centralized Office Building (COB)**
 - Repair by Replacement Office Building
 - Awarded through the SII Program in FY08
- **GRC advocacy for this project**
 - **Evaluation Factor 4: Management Approach**

“Glenn will initiate the creation of an independent, third party team to perform a Preliminary Design Review (PDR) and a Critical Design Review (CDR) during the design phase of the project. The function of this PDR/CDR Team will be to review and control the project Requirements Document and ensure that all critical requirements are addressed by the final design. Glenn will request participation from NASA Headquarters and other field centers for this team.”

Glenn Research Center

Facilities Division

Lewis Field & Plum Brook Station



Why Is Glenn Doing a PDR?

- **Multiple Centers have been awarded Repair by Replacement Buildings**
 - Conformance to newly approved Center Master Plans
 - LEED Silver (minimum) and conform to stringent Energy Usage mandates
 - Utilize Building Information Modeling (BIM)


Hope to draw upon lessons learned from other Centers implementing new buildings!

- **Provide awareness to NASA Headquarters**

Glenn Research Center

Facilities Division

Lewis Field & Plum Brook Station



The Process for PDR

- **GRC Master Plan**

Joe Morris, GRC Chief Architect

- Overview of Approved Glenn Master Plan
- Define the site for the Centralized Office Building

- **Preliminary Design Review Presentation**

Eric Patton, GRC PM for the Centralized Office Building


Michael Carter, PM from Burt, Hill (A/E Firm)

- Identify project requirements
- How does the preliminary design meet the requirements
- Preliminary features of the Centralized Office Building

Glenn Research Center

Facilities Division

Lewis Field & Plum Brook Station




The Process for PDR

- **Established PDR Review Team**
 - Steve Rider, HQ/FERPD (Program Manager for GRC)
 - Rhonda Pepper, MSFC/AS21 ()
 - Soheila Dianati, ARC/JCE ()
 - Ralph Allen, MSFC/xxx ()
 - David Larson, GSFC
- **During PDR, only PDR Team to ask formal questions**
 - Questions from the general assembly can be addressed after the presentation
- **PDR Team can ask formal questions**
 - RFA Forms provided
 - Formal answers returned at Critical Design Review

Glenn Research Center

Facilities Division

Lewis Field & Plum Brook Station




Lewis Field Campus Master Plan – Presented by Joe Morris



Glenn Research Center


6

Lewis Field & Plum Brook Station



Lewis Field Campus Master Plan

- *12 projects over a 20 year period*



Glenn Research Center


7

Lewis Field & Plum Brook Station



Facility Goals

1. *Infrastructure + Cost reduction*
2. *Security*
3. *Prepare for Space Flight work*
4. *Public outreach*
5. *Improve campus image*





Lewis Field Campus Master Plan Concept



New Campus Center at Lewis Field

Figure 6.3 Campus Center Plan



90,000 sq. ft. LEED Silver

400 seats, 6000 sq. ft.

7 Meeting Rooms

Displays, Events and Gatherings


300+ desks

Glenn Research Center

Lewis Field & Plum Brook Station



Building Concepts similar to KSC OSB2



Project Site






Glenn Research Center

¹²
Lewis Field & Plum Brook Station






This photo is cropped from Pictometry
Glenn Research Center
Lewis Field & Plum Brook Station






Planned Location for new Centralized Office Building
First step toward Glenn's Campus Center

Campus Center Site Planning



OPTION 9

2. Campus Center Site Planning Concepts



Building Design Concepts



Building Concept



Glenn Research Center

G6QH9920

¹⁸
Lewis Field & Plum Brook Station



Preliminary Design Review (PDR)

for the new

Centralized Office Building


Presented by Eric Patton

At the

May 14, 2009 Facilities Symposium

Glenn Research Center

Lewis Field & Plum Brook Station



Project Goals and Requirements

Scope

- Provide a centralized office building to accommodate a minimum of 300+ desks in open and private offices featuring:
 - 6000 square foot 400 person flat floor auditorium
 - Conference Center with highly functional meeting rooms
 - Lobby space for displays, events, and gatherings

The project will include roadways, paved areas, underground utilities, and connection to institutional facility systems. The building area is programmed as approximately 80,000 to 90,000 gross square feet, three stories above grade, with at least 250 parking spaces.

- A warehouse is also being designed in conjunction with the COB, but will not be covered in this PDR.

Budget


- FY2008 FP&D funding for design and commissioning
- FY2010 Construction funding \$25.3M (\$20.5M for COB, \$4.4M for Warehouse, \$0.4M for project reserve)
- FY2011/12 \$4.7M of outfitting/activation costs requested from CM&O split over both years

Schedule

Occupancy by Spring of 2012.

Glenn Research Center

Lewis Field & Plum Brook Station




Schedule

					FY 2008					FY 2009					FY 2010					FY 2011					FY 2012																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Item	Description	Start	Complete	% Complete	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		

Glenn Research Center

Lewis Field & Plum Brook Station



Project Goals and Requirements

Quality

- Needs to be functional but not a Cadillac yet inspirational
- COB must be a high performance building
- Prefer spending budget on higher quality office vs. warehouse

Safety


- Design for Safety (design decision criteria)
- No lost time accident during construction

Coordination

- Implement construction with minimal impact to GRC operations
- Buildings 21 and 50 remain open throughout although B21 South Loading dock to be closed.
- Ares and/or follow-on manufacturing needs truck access to B50 High Bay from north end.
- Demolition of B28, B84, B137 to create open site for allowable footprint, construction layout and staging and eventually parking.

Glenn Research Center

Lewis Field & Plum Brook Station



Project Goals and Requirements

Leadership in Energy and Efficient Design (LEED)

- LEED “Silver” minimum
- A-E to balance LEED requirement with cost and quality; strive for “Gold”.
- Enhanced Commissioning

Building Information Modeling (BIM)


- Demonstrate use of technology as “pilot projects” for both COB and Warehouse.

NPR 8820

- Facility Project Management Plan (yet to be signed)
- Functional Requirements Document (signed off)
- Project Stakeholders
 - Code M, Space Flight Systems, Tim Tyburski
 - Code R, Research and Technology, Gloria Richards
 - Code D, Engineering, Bob Zalewski
- Project Definition Rating Index (PDRI)
 - First attempt scored at 456 prior to 30% design, anticipate less than 200 after 60%
- COB activation/outfitting
- Change Management

Glenn Research Center

Lewis Field & Plum Brook Station




Change Management


- Established and documented in the FPMP.
- Delegate decision-making as much as possible to the PM/Team
- Establish Change Control Board to approve all changes that impact cost by > \$100K or schedule by > 30 days.
- CCB membership consists of GRC Facilities Division Leadership Team:
 - Dallas Lauderdale, Chairman
 - Rick Danks, Alternate
 - Jim Onest, Operations Management Branch
 - Renee Palyo, Engineering Management Branch
 - Joe Morris, Facilities Planning Office
 - Joe Torri, Systems Management Branch
 - Gene Stygles, Project Management Branch
 - Mark Woodling, Program Management Office

Glenn Research Center


Lewis Field & Plum Brook Station



NASA Team Structure



A&E Team Structure




Introduction of Burt, Hill

- Burt, Hill is a full service, international design firm with 13 offices worldwide
- Over 900 employees.
- The firm has a specialty in Science related projects.
- A strong commitment to sustainability
 - Charter member of USGBC
 - CEO Harry Gordon was the first Architect to join the USGBC
 - Harry and Sustainability Director Gina Baker serve on the USGBC committee that write the LEED standards
 - Burt, Hill was part of the team that did the “Greening of the Whitehouse” project
 - Nine LEED certified buildings and over 35 registered.
- Firm wide commitment to BIM
 - Completing a 3year program to deploy BIM on 95% of projects
 - Beta testers for Revit software
 - Integrated design process
- Mike Carter is the Project Manger as well as the practice leader of the Cleveland office
 - 30 years experience in the practice of Architecture as a RA
 - Graduate of Miami University
 - Bachelor degree in Architecture
 - Masters Degree in Environmental Planning

Glenn Research Center

Lewis Field & Plum Brook Station



Preliminary Design Review

Presented by Mike Carter

B U R T , H I L L

Glenn Research Center

Lewis Field & Plum Brook Station




Design Process

- **Review Program prepared by NASA GRC team**
- **Discovery Workshop**
 - Gather available data
 - Utilities
 - Environmental Information
 - Discuss adjacencies/functionality
 - Visual Listening
 - Design charrette
 - LEED workshop
- **Re-visit the master plan**
 - Focus on Central Quad


Glenn Research Center

Lewis Field & Plum Brook Station



Pre-Design Process

- **Develop design using BIM to greatest extent possible**
 - Revit as design and energy modeling tool
- **Begin Energy Modeling Development**
 - Design is influenced by modeling of day lighting and energy usage





NASA Master Plan



Glenn Research Center

Lewis Field & Plum Brook Station






Glenn Research Center

Lewis Field & Plum Brook Station





Glenn Research Center

Lewis Field & Plum Brook Station



Program

Area Entry	SIZE			UNIT	CIRC.	UNIT	REQ'D	TOTAL	Comments
	L	x	W	NSF.	NSF.	USF.	QTY.	USF.	
Entry Vestibule	0	x	5	50	54	204	2	408	
Lobby	00	x	30	3000	264	3264	1	3264	Size offers more opportunities for display space and Conference Center pre-function.
TOTAL Usable Square Footage								3,672	
Offices Areas									
Small Workstation	7	x	9	63	36	99	253	25,047	Amount of secondary circulation provided in NASA program is not required.
Large Workstation	9	x	05	95	43	88	30	4,25	Amount of secondary circulation provided in NASA program is not required.
Director Office	0	x	5	50	54	204	5	3,060	
Supervisor Office	0	x	25	25	49	174	20	3,480	
Division Suite Reception (Support Staff)	0	x	25	250	74	324	5	1,620	
Workroom	0	x	8	80	60	240	0	2,400	
Collaboration Room (4 Seats)	0	x	0	00	44	144	2	1728	Requires additional space to accommodate 4 people and layout space.
Small Conference Room (6 Seats)	0	x	2	20	48	68	5	840	Requires additional space to accommodate 6 people.
Large Conference Room (25 Seats)	20	x	24	480	92	572	5	2,860	Requires additional space to accommodate 25 people.
VITS Conference Room	55	x	21	326	77	403	3	1,208	Size assumes layout shall match existing, with chairs around perimeter of room.
Collision / Break-Out Area	6	x	6	36	28	64	8	512	As discussed during design charrette.
TOTAL Usable Square Footage								46,880	
Conference Center									
Auditorium (400 Seats)	60	x	00	6,000	0	6,000	1	6,000	Assumes "lecture style" seating layout. Tables will require additional space.
A/V Projection Room	12	x	20	240	68	308	1	308	
Small Conference Room	5	x	20	300	74	374	4	1,496	
Medium Conference Room	20	x	44	880	82	1,012	1	1,012	
Large Conference Room	20	x	86	1,720	26	1,936	1	1,936	
VITS Conference Room	12	x	34	408	96	504	1	504	
Catering Kitchen	14	x	20	280	72	352	1	352	
Coffee / Vending	0	x	20	200	64	264	1	264	
Registration / Information	0	x	18	80	50	80	1	80	
Business Center	8	x	8	64	36	100	1	100	Typically required by Conference Center occupants. May be located adjacent to Registration.
Break-Out Areas	0	x	0	00	44	144	2	288	Typically required by Conference Center occupants.
Coat Room	6	x	20	320	76	396	1	396	Assumes 50% of Conference Center occupants are located within COB x 3" per coat.
Chair / Table Storage	20	x	36.5	730	17	847	1	847	May require additional space depending on furniture sizes, stacking capability and cart sizes.
Conference Material Storage	6.25	x	8	50	33	83	2	65	
TOTAL Usable Square Footage								18,848	

Glenn Research Center

Lewis Field & Plum Brook Station



Program

Common Spaces									
Toilet Rooms (Men's and Women's)	6	x	30	450	94	544	8	4,352	Two per floor, with Office Area.
Shower / Dressing Room	0	x	0	00	44	114	2	288	Rooms are ADA compliant and include toilet, lavatory and shower.
Coffee / Vending	0	x	25	125	49	174	3	522	One per floor.
Storage	3	x	8	24	26	50	4	200	
Receiving	0	x	25	250	74	324	1	324	As discussed during design charrette.
Housekeeping / Janitorial	8	x	8	64	36	100	3	300	One per floor.
Mechanical Spaces and Chases	55	x	10	5500	311	5811	1	5811	
Additional MEP Spaces	30	x	50	1500	164	1664	1	1664	Larger Electrical Rm, separate Generator Rm. and additional mechanical spaces may be required.
Electrical Rooms	5	x	8	40	30	70	6	420	Two closets per floor.
Elevator Machine Room	0	x	0	00	44	114	1	114	
Data / Communication Rooms	0	x	0	00	44	114	3	432	One per floor.
Server Room	6	x	0	60	36	96	3	288	One per floor.
Building Stair	0	x	20	200	64	264	6	1684	Two per floor.
Elevators	0	x	30	300	84	384	3	152	One bank per floor.
TOTAL Usable Square Footage								7,484	
Sub-total								8,184	
Primary Circulation Factor (10%)								8,184	
Total								90,072	

GENERAL NOTES:

Primary circulation is 10% of program sub-total.

Secondary circulation is included in Usable Square Foot Totals.

Three floors are assumed for the time being.

Double height space of Lobby and Auditorium may affect Program Total.

Atrium floor space has not been accounted for in Program Total

Usable green roof may be added for additional Meeting and Collaboration Spaces.

Glenn Research Center

Lewis Field & Plum Brook Station



Visual Listening



Glenn Research Center


Lewis Field & Plum Brook Station





Glenn Research Center


Lewis Field & Plum Brook Station







Glenn Research Center

Lewis Field & Plum Brook Station





Glenn Research Center

Lewis Field & Plum Brook Station



Sustainable Design

LEED 2.2 Checklist Summary

Sustainable Sites
Water
Energy & Atmosphere
Conserving Materials & Resources
Enhance Indoor Environmental Quality
Innovation in Design
Totals

Possible	Probable	Potential	Not Possible
14	8	5	1
5	3	1	1
17	11	4	2
13	4	4	5
15	11	3	1
5	2	3	0
69	39	17	10

LEED Certified 26 – 32
 Silver 33 – 38
 Gold 39 – 51
 Platinum 52 or more

Certified 26-32 points
 Silver 33-38 points
 Gold 39-51 points
 Platinum 52+ points


Glenn Research Center

Lewis Field & Plum Brook Station



Energy Modeling Strategy


- Daylighting and Energy Efficiency should drive design
- Maximize North Lighting
- High Efficiency skin strategy
- Incorporate BIM and IES



Total Building


42,300 sf External Wall

Vertical Glazing, 49% of Wall



Glenn Research Center

Lewis Field & Plum Brook Station




1st Floor

57% above 25fc

25,500 sf “regularly occupied”
(Lobbies, offices, conference)

lm/ft²


95
85
75
65
55
45
35
25
15
5



Glenn Research Center

Lewis Field & Plum Brook Station






The effect of adjusting middle window size was
studied for the 2nd Floor South Open Office


Glenn Research Center

Lewis Field & Plum Brook Station



2nd Floor South Office
No middle Window (Preliminary Design)

lm/ft²
95
85
75
65
55
45
35
25
15
5



Glenn Research Center


Lewis Field & Plum Brook Station



2nd Floor South Office
56ft Window

lm/ft²

95	—
85	—
75	—
65	—
55	—
45	—
35	—
25	—
15	—
5	—




Glenn Research Center

Lewis Field & Plum Brook Station



56ft Window
Sunny

lm/ft²
95
85
75
65
55
45
35
25
15
5



Glenn Research Center

Lewis Field & Plum Brook Station




Summary


- **Preliminary Daylight Fenestration Design**
 - 53% occupied space above 25fc
 - Does not fulfill LEED EQ credit 8.1
 - Vertical Glazing 49% of External Wall
 - Exceeds ASHRAE Baseline
- **Focus daylight harvesting on lobby areas**
 - Lower light levels are required
 - Central light well
- **Daylight office perimeters as much as possible without exceeding 40% total glazing area**
 - Minimize East and West glazing
 - Maximize daylight harvesting on 3rd floor with Skylights
 - Slope ceilings over 15ft perimeter (13ft down to 10ft)
 - Use dimming ballasts only within 20ft perimeter

Glenn Research Center

Lewis Field & Plum Brook Station



BLDG. 21




TAYLOR ROAD

Glenn Research Center

Lewis Field & Plum Brook Station





Glenn Research Center

Lewis Field & Plum Brook Station





1 FIRST FLOOR BLOCK PLAN - 33,773 GSF

APRIL 21, 2009

LEGEND:



CORE / COMMON AREA



CONFERENCE CENTER



OFFICE AREA (FULL HEIGHT PARTITIONS)



1 SECOND FLOOR BLOCK PLAN - 28,319 GSF (27,386 SF MINUS VOIDS)
NTS

APRIL 21, 2008

LEGEND:




CORE / COMMON AREA



CONFERENCE CENTER




OFFICE AREA (FULL HEIGHT PARTITIONS)



Glenn Research Center

Lewis Field & Plum Brook Station




View from West



Glenn Research Center

Lewis Field & Plum Brook Station




View from East



Glenn Research Center

Lewis Field & Plum Brook Station




View of Lobby looking east



Glenn Research Center

Lewis Field & Plum Brook Station



Questions

Glenn Research Center

Lewis Field & Plum Brook Station

